



7. Will a surveyor be marking out the locations for flush mount handholes?  
*Yes a surveyor will provide ground markings and/or staking throughout the project area.*
8. When crossing underground utilities we are required to expose the utility which will require a lot of concrete and asphalt cuts. Will this bid require us to remove and replace any and all asphalt and concrete cuts needed to expose existing utilities?  
*Yes, utilities will need to be located prior to start of conduit install and removal of asphalt and concrete may be necessary by GC.*
9. Or will we be filling in open cuts with gravel?  
  
*This will depend on the timing of other phases of the project. Gravel will likely be sufficient for the majority of project areas on Front and Water Street. Asphalt patch will need to be installed on Main Street conduit sections.*
10. Will we need to use road cores to expose utilities under the main roads for road crossings? GC will need to locate utilities along conduit route prior to construction. The selected contractor can use coring, potholing, if absolutely necessary. The preference would be to utilize ground penetration radar where possible.
11. Is there a separate bid for asphalt and concrete work? Can I get a copy of the Invitation to Bid for the asphalt and concrete work?

All active bid solicitations can be found at:  
<https://www.franklintonnc.gov/procurement>